Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
			4	1.50	1.50	0.15	1.35		
	For Flooring		1	4.70	4.10	0.15	2.89		
	Bharathnagara								
	For Wall Portion		1	18.40	0.90	0.15	2.48		
			4	1.50	1.50	0.15	1.35		
	For Flooring		1	4.70	4.10	0.15	2.89		
	R.K. Hegdenagara 2								
	For Wall Portion		1	18.40	0.90	0.15	2.48		
			4	1.50	1.50	0.15	1.35		
	For Flooring		1	4.70	4.10	0.15	2.89		
					Total Qty		**81.19**		
					Qty Limited		**80.68**	**4836.00**	**390168.48**
56	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work								
		Cum							
	Kogilu								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	Kogilu layout								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	Kattigenehalli								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	Agrahara layout								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	Agrahara village								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	Basavalingappa nagara								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	Jakkur village								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	R.K. Hegdenagara 1								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	Saraipalya								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	Thanisandra								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
	Bharathnagara								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
	R.K. Hegdenagara 2								
	For Wall Portion		1	18.40	0.75	0.60	8.28		
	Deduction for Columns		4	1.50	0.75	0.60	-2.70		
							66.96	**4160.00**	**278553.60**
57	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work								
		Cum							
	Kogilu								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	Kogilu layout								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	Kattigenehalli								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	Agrahara layout								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	Agrahara village								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	Basavalingappa nagara								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	Jakkur village								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	R.K. Hegdenagara 1								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	Saraipalya								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	Thanisandra								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	Bharathnagara								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
	R.K. Hegdenagara 2								
	For Wall Portion		1	18.40	0.45	0.45	3.73		
	Deduction for Columns		4	1.50	0.45	0.45	-1.22		
							30.13	**4973.00**	**149846.44**

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
58	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification No. KBS 2.9 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work								
		Cum							
	Kogilu								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	Kogilu layout								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	Kattigenehalli								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	Agrahara layout								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	Agrahara village								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	Basavalingappa nagara								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	Jakkur village								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	R.K. Hegdenagara 1								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	Saraipalya								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	Thanisandra								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	Bharathnagara								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
	R.K. Hegdenagara 2								
	Centre Line		1	18.40	0.90	0.80	13.25		
	Columns		4	1.50	1.50	1.20	10.80		
							288.58	**126.00**	**36360.58**
59	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4. with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work								
		Sqm							
	Kogilu								

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	Kogilu layout								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	Kattigenehalli								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	Agrahara layout								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	Agrahara village								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	Basavalingappa nagara								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	Jakkur village								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
	For Steps		1	4.10		0.10	0.41		
	For Flagging Course		2	7.50		0.40	6.00		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	R.K. Hegdenagara 1								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	For Flagging Course		2	5.00		0.40	4.00		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	Saraipalya								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	Thanisandra								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	Bharathnagara								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
	R.K. Hegdenagara 2								
	For Wall Portion		2	5.10		3.00	30.60		
			2	4.10		3.00	24.60		
	For Parapet Wall		2	5.55		0.40	4.44		
			2	4.10		0.40	3.28		
	For Steps		1	4.10		0.10	0.41		
	Deduction for Rolling Shutter		1	3.04		2.50	-7.60		
	Deduction for Ventilator		2	0.60		0.90	-1.08		
							665.80	**931.00**	**619859.80**

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
60	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1,4.6, with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work								
		Cum							
	Kogilu								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Kogilu layout								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.74		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Kattigenehalli								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Agrahara layout								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Agrahara village								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Basavalingappa nagara								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Jakkur village								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	R.K. Hegdenagara 1								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Saraipalya								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Thanisandra								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Bharathnagara								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	R.K. Hegdenagara 2								
	For Footings		4	1.20	1.20	0.50	2.88		
	For Columns		4	0.23	0.23	3.80	0.80		
	For Plinth Beam		1	18.40	0.20	0.20	0.73		
	For Lintel		1	18.40	0.20	0.15	0.55		
	For Roof Slab		1	5.55	4.50	0.125	3.12		
	Bengaluru One								
	Vinayakanagara								
	For Footings		8	1.20	1.20	0.50	5.76		
	For Columns		4	0.20	0.35	4.90	1.37		
			4	0.20	0.35	5.90	1.65		
	For Plinth Beam		1	26.70	0.20	0.30	1.60		
	Agrahara layout								
	For Footings		8	1.20	1.20	0.50	5.76		
	For Columns		8	0.20	0.35	4.90	2.74		
	For Plinth Beam		1	26.70	0.20	0.30	1.60		
	Dasarahalli								
	For Footings		8	1.20	1.20	0.50	5.76		
	For Columns		8	0.20	0.35	4.90	2.74		
	For Plinth Beam		1	26.70	0.20	0.30	1.60		
							127.66	**5973.00**	**762509.95**

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
61	KSRB 4.2.8: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, and beams retaining walls, return walls, walls (any thickness) including attached plasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6. with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work								
	Bengaluru One	**Cum**							
	Vinayakanagara								
	For Lintel		1	26.70	0.20	0.15	0.80		
	For Roof Beam		1	35.80	0.20	0.45	3.22		
	For Roof Slab		1	4.95	7.60	0.15	5.64		
			1	5.35	0.90	0.15	0.72		
	Agrahara layout								
	For Lintel		1	26.70	0.20	0.15	0.80		
	For Roof Beam		1	35.80	0.20	0.45	3.22		
	For Roof Slab		1	4.95	7.60	0.15	5.64		
			1	5.35	0.90	0.15	0.72		
	Dasarahalli								
	For Lintel		1	26.75	0.20	0.15	0.80		
	For Roof Beam		1	35.80	0.20	0.45	3.22		
	For Roof Slab		1	4.95	7.60	0.15	5.64		
			1	5.35	0.90	0.15	0.72		
							31.17	**6119.00**	**190706.28**
62	KSRB 4.2.10 : Providing and laying in position reinforced cement concrete ofmix M20 with OPC cement @ 24kgs, with 12 mm and down size graded granite metal coarse aggregates @ 0.5175 cum and fine aggregates @ 0.345 cum with superplastisiser @ 0.225lts,machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor lever, including cost of all materials, labour, HOM of machinery, curing, complete as per specification. Specification NO. KBS 4.1, 4.6 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work								
		Cum							
	Kogilu								
	For Chejja		2	1.20	0.45		1.08		
	Kogilu layout								
	For Chejja		2	1.20	0.45		1.08		
	Kattigenehalli								
	For Chejja		2	1.20	0.45		1.08		
	Agrahara layout								
	For Chejja		2	1.20	0.45		1.08		
	Agrahara village								
	For Chejja		2	1.20	0.45		1.08		
	Basavalingappa nagara								
	For Chejja		2	1.20	0.45		1.08		
	Jakkur village								
	For Chejja		2	1.20	0.45		1.08		
	R.K. Hegdenagara 1								

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
	For Chejja		2	1.20	0.45		1.08		
	Saraipalya								
	For Chejja		2	1.20	0.45		1.08		
	Thanisandra								
	For Chejja		2	1.20	0.45		1.08		
	Bharathnagara								
	For Chejja		2	1.20	0.45		1.08		
	R.K. Hegdenagara 2								
	For Chejja		2	1.20	0.45		1.08		
	Bengaluru One								
	Vinayakanagara								
	For Chejjas		8	1.40	0.90		10.08		
	Agrahara layout								
	For Chejjas		8	1.40	0.90		10.08		
	Dasarahalli								
	For Chejjas		8	1.40	0.90		10.08		
							43.20	**453.00**	**19569.60**
63	KSRB 4.9.1: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work								
		MT							
			7				0.964		
			5				0.964		
			2				2.321		
			1				2.321		
							6.748		
							4.82		
							4.642		
							2.321		
							18.53	**69075.00**	**1280028.83**
64	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work								
		Sqm							
	Kogilu								
	For Footings		4	4.80		0.50	9.60		
	For Columns		4	0.92		4.00	14.72		
	For Plinth Beam		1	18.40		0.20	3.68		
	For Lintel		1	18.40		0.15	2.76		
	For Roof Slab		1	5.55	4.50		24.98		
	For Sides		2	5.55		0.15	1.67		
			2	4.50		0.15	1.35		
	Kogilu layout								
	For Footings		4	4.80		0.50	9.60		
	For Columns		4	0.92		4.00	14.72		
	For Plinth Beam		1	18.40		0.20	3.68		

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
	For Lintel		1	18.40		0.15	2.76		
	For Roof Slab		1	5.55	4.50		24.98		
	For Sides		2	5.55		0.15	1.67		
			2	4.50		0.15	1.35		
	Kattigenehalli								
	For Footings		4	4.80		0.50	9.60		
	For Columns		4	0.92		4.00	14.72		
	For Plinth Beam		1	18.40		0.20	3.68		
	For Lintel		1	18.40		0.15	2.76		
	For Roof Slab		1	5.55	4.50		24.97		
	For Sides		2	5.55		0.15	1.66		
			2	4.50		0.15	1.35		
	Agrahara layout								
	For Footings		4	4.80		0.50	9.60		
	For Columns		4	0.92		4.00	14.72		
	For Plinth Beam		1	18.40		0.20	3.68		
	For Lintel		1	18.40		0.15	2.76		
	For Roof Slab		1	5.55	4.50		24.97		
	For Sides		2	5.55		0.15	1.66		
			2	4.50		0.15	1.35		
	Agrahara village								
	For Footings		4	4.80		0.50	9.60		
	For Columns		4	0.92		4.00	14.72		
	For Plinth Beam		1	18.40		0.20	3.68		
	For Lintel		1	18.40		0.15	2.76		
	For Roof Slab		1	5.55	4.50		24.97		
	For Sides		2	5.55		0.15	1.66		
			2	4.50		0.15	1.35		
	Basavalingappa nagara								
	For Footings		4	4.80		0.50	9.60		
	For Columns		4	0.92		4.00	14.72		
	For Plinth Beam		1	18.40		0.20	3.68		
	For Lintel		1	18.40		0.15	2.76		
	For Roof Slab		1	5.55	4.50		24.97		
	For Sides		2	5.55		0.15	1.66		
			2	4.50		0.15	1.35		
	Jakkur village								
	For Footings		4	4.80		0.50	9.60		
	For Columns		4	0.92		4.00	14.72		
	For Plinth Beam		1	18.40		0.20	3.68		
	For Lintel		1	18.40		0.15	2.76		
	For Roof Slab		1	5.55	4.50		24.97		
	For Sides		2	5.55		0.15	1.66		
			2	4.50		0.15	1.35		
	R.K. Hegdenagara 1								
	For Footings		4	4.80		0.50	9.60		
	For Columns		4	0.92		4.00	14.72		
	For Plinth Beam		1	18.40		0.20	3.68		
	For Lintel		1	18.40		0.15	2.76		
	For Roof Slab		1	5.55	4.50		24.97		
	For Sides		2	5.55		0.15	1.66		
			2	4.50		0.15	1.35		

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
	Opp. To Railway Bridge, Thanisandra		6	580.00			3480.00		
	Rachenahalli Main Road		15	580.00			8700.00		
	P & T Colony		18	580.00			10440.00		
	Royal Welfare Association Road		7	580.00			4060.00		
	Near Chinmayi Vidyanikethan School		2	580.00			1160.00		
	Near Regacy Pinacle Appartments		2	580.00			1160.00		
	MCECHS Layout		75	580.00			43500.00		
	Shivaramakaranth Nagara		12	580.00			6960.00		
	BDS Layout		14	580.00			8120.00		
	Shiradi Sai Layout		16	580.00			9280.00		
	Old Boards								
	Rachenahalli		51	580.00			29580.00		
	Thanisandra		63	580.00			36540.00		
	Amarajyothi Layout		45	580.00			26100.00		
	Ashwathnagara		37	580.00			21460.00		
	Bharathnagara		35	580.00			20300.00		
	R.K. Hegdenagara		79	580.00			45820.00		
							319000.00	0.49	156310.00
128	Manufacturing, Supply & Fixing of Retro- Reflection Road name sign board single Arrow size 1.98X0.9m size made out if wide angle cube corner micro prismatic grade sheeting confirming to IRC 67:2010 & type XI standards of ASTM D 4956-09 specifications and fixed over 2mm thick aluminium sheet back support frame of stainless stell supported by 30NB 1.2mm thick stainless steel pipe all around and 65NB 1.5mm thick pipe vertical post (AISI 202 Grade) firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 30cmx30cmx45cm etc.complete.								
	Retro- Reflection Boards	Each							
	Thanisandra & R.K. Hegdenagara		12				12.00	25890.00	310680.00
	EIRL								
	Furniture								
E1	Workstation table finishing venner inside laminated border Silver, top granite with key board tray etc complete cost inclusive of materials, labours, transportation all taxes etc complete								
		Nos							
			2x3				6.00	14501.80	87010.80
	Approved Rate	15500.00							
	Tender Premium @ -6.44%	-998.20							
	Total	14501.80							
E2	Pedal Unit 3 Drawers								
		Nos							
			1x3				3.00	8420.40	25261.20
	Approved Rate	9000.00							
	Tender Premium @ -6.44%	-579.60							
	Total	8420.40							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
E3	Providing and fixing storage unit of 0.75m width made out of 19mm thick commercial ply vertical support finished in approved 1.5mm laminate with 12mm thick ply packing internally finished with enamel paint of approved colour and shade shelves shall be formed out of 19mm ply finished with enamel paint of approved shade and colour and 19mm thick shutters formed out of 19mm thick ply finished with 1.5mm thick laminate of approved shade and colour etc., complete the rate includes cost of all materials, labour charges, complete as per specification.(P.No. 324, I.No. 39.4 of SR 2018-19)								
		Sqm							
			3	2.10		1.50	9.45	13206.56	124801.95
	Basic Rate	13070.00							
	Area Weightage @ 8%	1045.60							
	Sub Total	14115.60							
	Tender Premium @ -6.44%	-909.04							
	Total	13206.56							
E4	Steel Executive revalving chair with cane ear back etc cost inclusive of materials, labours, transportation all taxes etc complete (DSMS Approved Rate)								
		Each							
			6x3				18.00	4210.20	75783.60
	Approved Rate	4500.00							
	Tender Premium @ -6.44%	-289.80							
	Total	4210.20							
E5	Visitor chair with cushion seat back with MS round pipe etc complete cost inclusive of materials, labours, transportation all taxes etc complete (DSMS Approved rates)								
		Each							
			2x3				6.00	5473.26	32839.56
	Approved Rate	5850.00							
	Tender Premium @ -6.44%	-376.74							
	Total	5473.26							
E6	Concealed Conduit System Supplying heavy gauge PVC conduit pipe .....mm dia .....mm thick confirming to IS 2509 with suitable size bends, metal/PVC junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary19/20mm dia 2mm thick	R/Mtrs	90.00				90.00	40.23	3620.77
	Basic Rate	43.00							
	Tender Premium @ -6.44%	-2.77							
	Total	40.23							
E7	25mm dia 2mm thick	R/Mtrs	55.00				55.00	53.33	2933.11
	Basic Rate	57.00							
	Tender Premium @ -6.44%	-3.67							
	Total	53.33							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
E8	Supplying heavy gauge PVC Conduit Pipe ….dia .....mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. 19/20 mm dia 2mm thick		75.00				75.00	52.39	3929.52
	Basic Rate	**56.00**							
	Tender Premium @ -6.44%	**-3.61**							
	Total	**52.39**							
E9	25mm dia 2mm thick	Mtr	35.00				35.00	54.26	1899.27
	Basic Rate	**58.00**							
	Tender Premium @ -6.44%	**-3.74**							
	Total	**54.26**							
E10	Supplying And Fixing Metal Fan Box with Round Hook.	No	9.00				9.00	86.08	774.68
	Basic Rate	**92.00**							
	Tender Premium @ -6.44%	**-5.92**							
	Total	**86.08**							
E11	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall1-3Way	Each	6.00				6.00	85.14	510.84
	Basic Rate	**91.00**							
	Tender Premium @ -6.44%	**-5.86**							
	Total	**85.14**							
E12	4-5Way	Each	6.00				6.00	91.69	550.13
	Basic Rate	**98.00**							
	Tender Premium @ -6.44%	**-6.31**							
	Total	**91.69**							
E13	6Way	Each	6.00				6.00	113.21	679.25
	Basic Rate	**121.00**							
	Tender Premium @ -6.44%	**-7.79**							
	Total	**113.21**							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
E14	Point wiring using Copper wire without switch. Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2X1.5Sq.mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block complete for each outlet.GROUP BShort point upto 3Mtr from tapping point to out let via switch box	Point	19.00				19.00	121.63	2310.93
	Basic Rate	130.00							
	Tender Premium @ -6.44%	-8.37							
	Total	121.63							
E15	Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch box	Point	10.00				10.00	177.76	1777.64
	Basic Rate	190.00							
	Tender Premium @ -6.44%	-12.24							
	Total	177.76							
E16	Long point above 6Mtr upto 10Mtr from tapping point to out let via switch box	Point	10.00				10.00	272.26	2722.60
	Basic Rate	291.00							
	Tender Premium @ -6.44%	-18.74							
	Total	272.26							
E17	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.1 to 3 Module		6.00				6.00	101.98	611.88
	Basic Rate	109.00							
	Tender Premium @ -6.44%	-7.02							
	Total	101.98							
E18	4 Module	Each	6.00				6.00	114.14	684.86
	Basic Rate	122.00							
	Tender Premium @ -6.44%	-7.86							
	Total	114.14							
E19	6 Module	Each	6.00				6.00	161.86	971.15
	Basic Rate	173.00							
	Tender Premium @ -6.44%	-11.14							
	Total	161.86							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
E20	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP B 6Amps one way.		54.00				54.00	46.78	2526.12
	Basic Rate	50.00							
	Tender Premium @ -6.44%	-3.22							
	Total	46.78							
E21	6Amps 3way socket.	Each	15.00				15.00	72.04	1080.62
	Basic Rate	77.00							
	Tender Premium @ -6.44%	-4.96							
	Total	72.04							
E22	Stepped Fan Regulator.	Each	9.00				9.00	220.80	1987.21
	Basic Rate	236.00							
	Tender Premium @ -6.44%	-15.20							
	Total	220.80							
E23	16Amps one way switch	Each	6.00				6.00	86.08	516.45
	Basic Rate	92.00							
	Tender Premium @ -6.44%	-5.92							
	Total	86.08							
E24	6/16Amps universal socket	Each	6.00				6.00	112.27	673.63
	Basic Rate	120.00							
	Tender Premium @ -6.44%	-7.73							
	Total	112.27							
E25	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper conductor single core wire in open or concealed system of wiring as per IS-694:1990 & confirming to GTP of GROUP -B.1.5 sqmm	Mtrs	300.00				300.00	14.88	4462.81
	Basic Rate	15.90							
	Tender Premium @ -6.44%	-1.02							
	Total	14.88							
E26	2.5 sqmm	Mtrs.	450.00				450.00	23.30	10483.40
	Basic Rate	24.90							
	Tender Premium @ -6.44%	-1.60							
	Total	23.30							
E27	4 sqmm	Mtrs.	300.00				300.00	33.96	10188.68
	Basic Rate	36.30							
	Tender Premium @ -6.44%	-2.34							
	Total	33.96							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
E28	LED Indoor Supplying of 4' feet - LED PVC Square Batten ..W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50Hz & Power factor >0.9 along with CE approved drivers. 5 years Warranty against any manufacturing defect working under standard electrical condition LED light fighting 4' - 28 watts	Nos	11.00				11.00	1659.75	18257.30
	Basic Rate	**1774.00**							
	Tender Premium @ -6.44%	**-114.25**							
	Total	**1659.75**							
E29	Supplying exhaust fan of 1440 RPM of 300mm (12") size with bracket blades complete for light duty suitable to operate on 230V 50Hz, AC Supply.	Nos	3.00				3.00	1590.52	4771.56
	Basic Rate	**1700.00**							
	Tender Premium @ -6.44%	**-109.48**							
	Total	**1590.52**							
E30	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. 48" Sweep (1200mm)Regular model	Nos	9.00				9.00	1777.64	15998.76
	Basic Rate	**1900.00**							
	Tender Premium @ -6.44%	**-122.36**							
	Total	**1777.64**							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
E31	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete 16SWG	Sqcms	16200.00				16200.00	0.31	5001.72
	Basic Rate	**0.33**							
	Tender Premium @ -6.44%	**-0.02**							
	Total	**0.31**							
E32	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.II - Double Door4Way SP &N	Nos	3.00				3.00	998.29	2994.86
	Basic Rate	**1067.00**							
	Tender Premium @ -6.44%	**-68.71**							
	Total	**998.29**							
E33	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.5-32Amps SP	Nos	9.00				9.00	391.08	3519.73
	Basic Rate	**418.00**							
	Tender Premium @ -6.44%	**-26.92**							
	Total	**391.08**							
E34	5-32 Amps DP	Nos	3.00				3.00	794.32	2382.97
	Basic Rate	**849.00**							
	Tender Premium @ -6.44%	**-54.68**							
	Total	**794.32**							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
E35	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.32Amps	Nos	6.00				6.00	42.10	252.61
	Basic Rate	**45.00**							
	Tender Premium @ -6.44%	**-2.90**							
	Total	**42.10**							
E36	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A.3.5 core 25 sqmm	Mtrs	110.00				110.00	154.94	17042.89
	Basic Rate	**165.60**							
	Tender Premium @ -6.44%	**-10.66**							
	Total	**154.94**							
E37	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct.25 sqmm to 75	Mtrs	110.00				110.00	16.20	1782.00
	Basic Rate	**16.20**							
	Tender Premium @ -6.44%	**-1.04**							
	Total	**15.16**							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
E38	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia	No	3.00				3.00	2551.38	7654.14
	Basic Rate	**2727.00**							
	Tender Premium @ -6.44%	**-175.62**							
	Total	**2551.38**							
E39	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7)In soil (ordinary)	Mtrs	100.00				100.00	72.98	7297.68
	Basic Rate	**78.00**							
	Tender Premium @ -6.44%	**-5.02**							
	Total	**72.98**							
E40	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV.40mm	Mtrs	12.00				12.00	322.78	3873.38
	Basic Rate	**345.00**							
	Tender Premium @ -6.44%	**-22.22**							
	Total	**322.78**							
E41	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.25Sqmm	Nos	3.00				3.00	338.69	1016.06
	Basic Rate	**362.00**							
	Tender Premium @ -6.44%	**-23.31**							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
	Total	**338.69**							
E42	Fixing halogen/metal halide / SVL / IL / LED floodlight fitting over existing pole / wall ceiling including clamps, bolts, nuts and wiring using suitable capacity wires.	Nos	15.00				**15.00**	164.67	**2469.98**
	Basic Rate	**176.00**							
	Tender Premium @ -6.44%	**-11.33**							
	Total	**164.67**							
E43	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps.On wall / ceiling / Rafter / Girders	Nos	20.00				**20.00**	91.69	**1833.78**
	Basic Rate	**98.00**							
	Tender Premium @ -6.44%	**-6.31**							
	Total	**91.69**							
E44	Fixing a ceiling / Wall mounting fan of all capacities and all types to the existing 'S' hook with fan regulator to the existing board together with supplying and fixing 5 amps. ceiling rose, necessary length of 23 / 0.0076 inch PVC insulated twin twisted copper wire and wiring.	Nos	9.00				**9.00**	130.05	**1170.44**
	Basic Rate	**139.00**							
	Tender Premium @ -6.44%	**-8.95**							
	Total	**130.05**							
E45	Supplying, erecting, testing & commissioning of OFF-LINE UPS system suitable for operation on 230V, 50Hz, A/C supply, with all accessories complete and Excluding batteries and wiring complete. 5 KVA OFF LINE UPS Two Hour back up Excluding 6x 120Ah batteries	Nos	3.00				**3.00**	47054.13	**141162.39**
	Basic Rate	**50293.00**							
	Tender Premium @ -6.44%	**-3238.87**							
	Total	**47054.13**							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
E46	Supplying, installation, testing & commissioning of 12V DC, AH batteries in poly propylene container for U.P.S. Low maintenance Tubular batteries.12 V ,12 V ,150 AH capacity. Acid Battery.	Nos	9.00				9.00	19273.36	173460.24
	Basic Rate	20600.00							
	Tender Premium @ -6.44%	-1326.64							
	Total	19273.36							
E47	Supplying and Fixing of.....mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires.Using 32mm dia G.I.pipe	Nos	20.00				20.00	835.49	16709.82
	Basic Rate	893.00							
	Tender Premium @ -6.44%	-57.51							
	Total	835.49							
E48	LED Street light.Supply of LED Streetlight with pressure die cast aluminum housing body with optimal heat sink for better thermal dissipation. Diffuser with Injection moulded & is made of polycarbonate material with high transmission index, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminare > IK08. Power Factor >0.9 with mains Current should not be greater than 0.1A to 0.7A & Surge Protection- Min 4KV along with Over voltage/Overload, short circuit/ miswiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V	Nos	22.00				22.00	17514.43	385317.50
	Basic Rate	18720.00							
	Tender Premium @ -6.44%	-1205.57							

Item No	Description of Work	Unit	No.	L	B	D	Qty	Rate	Amount
	Total	**17514.43**							
	BESCOM Deposit								
	Dasarahalli Bangalore One		4840+149+149+650+1000+671						**7459.00**
	Agrahara Layout Bangalore One		672+4840+5+5+19+19+50+212						**5822.00**
	Borewells								
	Basavalingappa Nagara		10200+9+9+100+1731						**12049.00**
	Dasarahalli Colony		12910+9+9+100+1731						**14759.00**
	Agrahara Layout Govt School Backside		15070+9+9+100+1731						**16919.00**
	Kogilu Sandeep Unikrishnan Layout		14280+9+9+100+1731						**16129.00**
	Jakkur, near Govt School		12240+9+9+100+1731						**14089.00**
	Agrahara Layout, Thirumenahalli Main Road		10200+9+9+100+1731						**12049.00**
	Kattigenahalli near Ward Office		10200+9+9+100+1731						**12049.00**
	Thanisandra near SLV School		12240+9+9+100+1731						**14089.00**
	Hegdenagara near Police Quotries		14280+9+9+100+1731						**16129.00**
	Bharathnagara near Manyatha Teck Park		10200+9+9+100+1731						**12049.00**
	RO Plant								
	Jakkur, near Govt School		4900+9+9+100+1731						**6749.00**
	Hegdenagara		5170+9+9+100+1731						**7019.00**
	Hegdenagara near Police Quotries		4900+9+9+100+1731						**6749.00**
	Agrahara Layout near Aswathkatte		4900+9+9+100+1731						**6749.00**
	Kogilu Layout		4900+9+9+100+1731						**6749.00**
	Basavalingappa Nagara 1st Main		4900+9+9+100+1731						**6749.00**
	Agrahara Layout near Bus Stand		4900+9+9+100+1731						**6749.00**
	Kogilu near Indira Canteen		4900+9+9+100+1731						**6749.00**
	Kattigenahalli near Ward Office		4900+9+9+100+1731						**6749.00**
	Sarayee Playa		4900+9+9+100+1731						**6749.00**
	Thanisandra near Vetrniary Hospital		4900+9+9+100+1731						**6749.00**
									19000.00
	Total								**41150744.13**

Rupees Four Crore Eleven Lakh(s) Fifty Thousand Seven Hundred Forty Four And Paise Thirteen Only

CERTIFICATE:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per PWD SR of 2016-17 and Data Rate +/- Tender Premium.
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Junior Engineer
Ward No. 05 & 06

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Sub Division

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

Technical Sanction
Accorded For Rs 41150744.13
Head of A/C P3106
CER NO : 09 Dt: 09.02.19

TA CE (YNK)